



NOTE: KEYED NOTES ARE LISTED FOR A5.01 - A5.04 BUILDING SECTIONS. SOME NOTES LISTED BELOW MAY NOT APPLY TO THIS SHEET.

- SECTION KEY NOTES**
1. COMPOSITION SHINGLES OVER 15 POUND ROOFING FELT.
 2. PLYWOOD ROOF DECKING W/ PLY-CLIPS, 5/8 INCH THICK.
 3. ROOF TRUSSES, RE: STRUCTURAL.
 4. INSULATION R-30, (BATT).
 5. WEAP HOLES @ 3'-0" O.C. MAX. (TYP. ALL EXTERIOR BLOCK VENEER WALLS).
 6. GYPSUM WALLBOARD, 5/8 INCH THICK, PAINTED.
 7. WOOD STUDS, 2 INCHES X 4 INCHES, RE: STRUCTURAL.
 8. WINDOW, RE: SCHEDULE.
 9. CERAMIC TILE OVER THIN SET.
 10. 3/4" GYP. CONCRETE ON 3/4" T&G PLYWD. DECKING
 11. INSULATION R-15 WITH VAPOR BARRIER.
 12. CONTINUOUS 2 INCH X 4 INCH WOOD PLATES.
 13. FIRESTOP.
 14. CONTINUOUS 2 INCH X 6 INCH WOOD PLATES.
 15. WOOD FLOOR TRUSS, RE: STRUCTURAL.

- SECTION KEY NOTES (CONT.)**
16. WOOD STUDS, 2 INCHES X 6 INCHES AT 16 INCH CENTERS.
 17. CYPRESS BOARD SIDING
 18. TWYCK HOUSE WRAP.
 19. 5/8" GYP. LAP SHEATHING, (FIRE-RATED).
 20. FINISH FLOOR, RE: SCHEDULE.
 21. CONTINUOUS 2 INCH X 6 INCH DOUBLE WOOD PLATES, TREATED.
 22. SCHEDULED WOOD BASE.
 23. 20 MIL. FLEXIBLE FLASHING AT BASE OF VENEER WALL TO EXTEND UP 8" BEHIND SHEATHING BOARD AND OVERLAP CONC. SILL.
 24. GALVANIZED 26 GAUGE METAL DRIP EDGE WITH HEMMED EDGES, PAINTED.
 25. METAL GALV. WALL TIES, AS REQUIRED.
 26. WOOD TRIM, 1 INCH X 6 INCH, PAINTED.
 27. WOOD TRIM, 2 INCH X 4 INCH (KDAT), PAINTED.
 28. PRE-CASTE CONCRETE TRIM.
 29. TIMBER BEAM, RE: STRUCTURAL.
 30. WOOD BLOCKING, 2 INCH X 6 INCH, PAINTED.

- SECTION KEY NOTES (CONT.)**
31. NON-VENTED SOFFIT BOARD, -CYPRESS.
 32. WOOD FASCIA, 2 INCH THK., VERIFY SIZE W/ DETAIL, PAINTED.
 33. WOOD FASCIA, 2 INCH THK., VERIFY SIZE W/ DETAIL, PAINTED.
 34. INSULATION R-19, (BATT).
 35. STEEL GALV. METAL ANGLE, RE: STRUCTURAL.
 36. TRIM, 1 INCH X 6 INCH, PAINTED.
 37. FLEXIBLE FLASHING.
 38. VENTED SOFFIT BOARD, 1/4 INCH THICK, SMOOTH BY HARDE.
 39. WOOD TRIM, 1 INCH X 4 INCH, PAINTED.
 40. CONCRETE SLAB, RE: STRUCTURAL.
 41. SMOOTH FACE CONC. COURSE, MATCH SPLIT-FACE C.M.U. COLOR.
 42. CONCRETE CAP COURSE, MATCH SPLIT-FACE COLOR.
 43. METAL FLASHING, EXTEND UP WALL 8 INCHES.
 44. WOOD TRIM, 1 INCH X 2 INCH, PAINTED.
 45. WOOD FRAMING, 2X AT 24" O.C.
 46. WOOD JOIST, 2 INCH X 6 INCH.
 47. U.L. 1-HOUR RATED ASSEMBLY DESIGN L-528 SYSTEM NO.4.
 48. 12" THK. C.M.U. WALL.

- SECTION KEY NOTES (CONT.)**
49. WOOD LEDGER, 2 INCH X 6 INCH.
 50. SCHEDULED WOOD DOOR.
 51. 2 LAYERS 5/8" TYPE "C" GYP. BD., 4" OUT FROM THE RATED WALL, BOTH SIDES.
 52. ALUMINUM THRESHOLD UNIT, SET IN MASTIC.
 53. WOOD TRIM, 2 INCH X 6 INCH, PAINTED.
 54. VAPOR BARRIER, 6 MIL. POLYETHYLENE.
 55. CONCRETE GRADE BEAM, RE: STRUCTURAL.
 56. CONTINUOUS 2 INCH X 6 INCH WOOD PLATES.
 57. WOOD TRIM, 2 INCH X 4 INCH, PAINTED.
 58. 5/8" TYPE "C" GYP. BD. SCREWED TO METAL RC-1 CHANNELS AT 16" O.C., U.L. L-528 ASSEMBLY.
 59. ANCHOR BOLTS, RE: STRUCTURAL. SEAL PLATE WITH FOAM SEALANT.
 60. WOOD FASCIA, 2 INCH X 10", RE: STRUCTURAL.
 61. 2 LAYERS 1" GYP. SHEATHING TYPE "X" (2-HR RATING).
 62. WD. STOOL.
 63. CONCRETE CURB.
 64. SLOPE CONCRETE SLAB FLOOR, (PATIO, HALLWAY).

- SECTION KEY NOTES (CONT.)**
65. ROD AND SHELF, RE: SPECS.
 66. 5/8" GYP. SOFFIT BD. SCREWED TO METAL CHANNELS OR 5/8" TYPE "C" GOLD BOND GYP. BD. SCREWED DIRECTLY TO TRUSS.
 67. STEPS BEYOND, SHOWN DOTTED.
 68. 2X6 WD. OUTLOOKER AT 16" O.C.
 69. WD. TRUSS W/ CEILING BREAK, RE: STRUCTURAL.
 70. CAULK.
 71. PRESSURE TREATED WOOD PLATE, 2 INCH X 4 INCH.
 72. 1" MIN. GAP BETWEEN SIDING AND ROOFING.
 73. PLACE SHINGLES SET IN ROOF MASTIC OVER METAL FLASHING.
 74. METAL FLASHING.
 75. METAL CORNER BEAD.
 76. WOOD HEADER, 2 INCH X, RE: STRUCTURAL.
 77. LINE OF SLOPED CEILING.
 78. WOOD BLOCKING, 1 INCH X 8 INCH, PAINTED.
 79. SLOPED CEILING.
 80. "S" TYPE METAL FLUE.

- SECTION KEY NOTES (CONT.)**
81. STONE HEARTH
 82. PREFABRICATED FIREPLACE.
 83. 5/8" GYP. BD.
 84. STONE VENEER ON WALL
 85. 4"x4" BULL-RAIL RAILING, 2X6 HANDRAIL AT TOP
 86. SLOPE TO DRAIN.
 87. 3/4" WD. CAP.
 88. CASWORK, RE: SPECS.
 89. BOTTOM RAIL, METAL, 3/4 INCH X 3/4 INCH.
 90. G.I. STEP FLASHING.
 91. 2X CORNER TRIM.
 92. SC ROUND CHIMNEY CAP.
 93. 1-1/2" LTR.WT. CONC. ON 3/4" T&G PLYWD. DECKING OVER 2 PLY HOT MOP WATERPROOFING.
 94. CASING, RE: SPECS.
 95. ROD AND SHELF, RE: SPECS.
 96. AIRSPACE.
 97. INSULATION Baffle.

- SECTION KEY NOTES (CONT.)**
98. 5/8" FIRE CODE GYP. BD. SCREWED TO METAL RC-1 CHANNELS AT 12" O.C. U.L. DESIGN NO. P-522 (LOOSE INSUL.) OR U.L. DESIGN P-538 (16" O.C. W/ 20 GA. CHANNELS AND JAMES HARDI-TYPE "C" GYP. BD.)
 99. ALUMINUM POUR STOP.
 100. GRADE
 101. HIGH POINT, SHIM, POUR STOP 1/2".
 102. FIRE-SAFING.
 103. TWO (2) LAYERS 1" TYPE "X" GYP. BD. SET IN C-RUNNERS, SEAL TO DECK AND SLAB BELOW.
 104. HORIZ. C-RUNNER, RE: A-514 FOR DETAIL.
 105. ANGLE CLP, RE: A-514 FOR DETAIL.
 106. C-RUNNER, SET IN SEALANT.
 107. NJ-1 METAL CHIMNEY SHROUD.
 108. 26 GA. GALV. METAL CHASE CAP.
 109. 15 # FELT OVER 1/2" CDX PLYWD. SHEATHING.
 110. AT EACH INSIDE CORNER OF THE CHIMNEY CHASE PROVIDE THE FOLLOWING: 2X4X9" STUD STRONG BACK BRACING TO BOTTOM OF ROOF TRUSS. NAIL STRONG BACK TOGETHER AT 6" O.C. ATTACH STRONG BACK TO INSIDE CORNER OF CHIMNEY CHASE WITH 8 NAILS MIN. EQUALLY SPACED. AND/OR ALL STRONG BACKS AT BOTTOM CHORD OF ROOF TRUSS WITH BLOCKING AS NECESSARY.
 111. REFER TO FIREPLACE MANUFACTURER'S INSTALLATION INSTRUCTIONS TO COMPLY WITH ALL CLEARANCE AND INSTALLATION REQUIREMENTS.
 112. SPRING HINGE SIDE.
 113. SPRING HINGED 1/2" ACCESS DOOR AP-2 SEE ROOF PLANS FOR LOCATION.
 114. 1-1/2" PLYWD. PLATFORM.
 115. 2X6 DOOR OPENING FRAME.
 116. SF FIRESTOP SPACER AT CEILING LINE ABOVE FIREPLACE BOX.
 117. KAMP 22"x30" KRP-350 FR. FIRE RATED ACCESS DOOR W/ FLUSH KEY LOCK
 118. PORTABLE 10' EXTENSION LADDER, SHOWN HIDDEN FOR CLARIFICATION

- SECTION KEY NOTES (CONT.)**
135. 1"6" TIMBER POSTS.
 136. METAL SHEAT FLASHING OVER ROOF JOINTS
 137. DESIGNED WOOD BRACKETS FOR ADDL. STRENGTH (SEE DETAILS)
 138. WOOD WALEY AS NEEDED
 139. 4"x8" FRAMING AT SLOPE END
 140. RIGID INSULATION WITH VAPOR BARRIER AIR GAP(MIN 2")AT TOP (R-30 BATT).
 141. DESIGNED WOOD TRIM (SEE DETAILS)

- SECTION KEY NOTES (CONT.)**
142. DIAGONAL BRACES TO STRENGTHEN TRUSS
 143. METAL PLATE WITH SEAM BOLT AND SCREWED TO WOOD MEMBERS
 144. DOUBLE WOOD STUDS, 2 INCHES X 6 INCHES AT -- C/C (RE: STRUCTURAL).

- SECTION KEY NOTES (CONT.)**

- SECTION KEY NOTES (CONT.)**

- SECTION KEY NOTES (CONT.)**

- SECTION KEY NOTES (CONT.)**

- SECTION KEY NOTES (CONT.)**
119. DEMISING WALL, SHOWN HIDDEN FOR CLARIFICATION.
 120. CONTINUOUS 1/2" DRAFTSTOP.
 121. 2X6 FRAMING BETWEEN TRUSSES.
 122. ACCESS DOOR -AP2, IN CENTER DEMISING WALL.
 123. CONTINUOUS DRAFTSTOP ACROSS THIS AREA.
 124. METAL CAIN DETECTION RAIL.
 125. 1-1/2" DIA. METAL HANDRAIL.
 126. CLOSED RISER, 14 GA. BENT METAL.
 127. 1/2" METAL BALLUSTERS @ 4" O.C.
 128. 1-1/2"x1-1/2" STEEL TUBE.
 129. MC 10X8.4 CHANNEL STRINGER.
 130. 2" PRECASTE CONC. TREADS.
 131. STEEL ANGLE SHELF.
 132. METAL HANDRAIL WALL BRACKET.
 133. METAL SHEATHING OVER 3/4" THK. PLYWOOD/WOODEN DECKING
 134. 4"x14" TIMBER RAFTERS, TREATED AND PAINTED BELOW ROOF SHEATHING